



**Republika ng Pilipinas**  
Republic of the Philippines  
**Kagawaran ng TanggulangPambansa**  
Department of National Defense  
**DND PROPER BIDS AND AWARDS COMMITTEE**

**SUPPLEMENTAL BID BULLETIN NO. DND-P-2018-08-005**

This Supplemental Bid Bulletin No. DND-P-2018-08-005 is issued to inform prospective bidders of the following amendments, modifications and/ or clarifications on the items for the Repair/ Renovation of OSMA posted on the websites of the PhilGEPS and DND:

**Section I. Invitation to Bid**

FROM	TO
7. Bids shall be prepared in Seven (7) copies without assistance from any person in the DND or in any branch of the government. xxx	7. Bids shall be prepared in <i>Nine (9)</i> copies without assistance from any person in the DND or in any branch of the government. xxx

**Section III. Bid Data Sheet**

FROM	TO
ITB Clause 12.1(a) Tab B of the Eligibility Documents  Statement of all ongoing government and private contracts including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid.	ITB Clause 12.1(a) Tab B of the Eligibility Documents  Statement of all ongoing government and private contracts including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid. <i>* Value of Outstanding Works/ Undelivered Portion is the amount corresponding to the unperformed/ undelivered portion of an on-going project to exclude projects which are already completed but not yet paid.</i>
ITB Clause 12.1(a) Tab C of the Eligibility Documents  Statement of at least one (1) similar completed largest contract within the last five (5) years from the date of the opening of bids equivalent to at least fifty percent (50%) of the ABC.	ITB Clause 12.1(a) Tab C of the Eligibility Documents  Statement of at least one (1) similar completed largest contract within the last five (5) years from the date of the opening of bids equivalent to at least fifty percent (50%) of the ABC. <i>* Completed projects are those projects that have already been certified as completed by the end-user regardless if already paid or not.</i> <i>* Supporting documents as required in the form such as 1) Contract; 2) Certificate of</i>

	<i>Completion; and 3) Certificate of Acceptance are not anymore required to be submitted during the opening of bids but are subject to post-qualification.</i>
ITB Clause 12.1(a) Tab E of the Eligibility Documents  Valid Joint Venture Agreement (JVA), in case the joint venture is already in existence, or duly notarized statements from all potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bids is successful.	ITB Clause 12.1(a) Tab E of the Eligibility Documents  Valid Joint Venture Agreement (JVA), in case the joint venture is already in existence, or duly notarized statements from all potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bids is successful. <i>If not applicable, proponent must submit a separate sheet of paper stating "Not Applicable".</i>
ITB Clause 20.3  Each Bidder shall submit seven (7) copies of the first and second components of its bid. Xxx	ITB Clause 20.3  Each Bidder shall submit <i>nine (9)</i> copies of the first and second components of its bid. xxx

**SECTION VI. SPECIFICATIONS**

FROM	TO
Item No. G.2.  Supply/Installation of ACU including rough-in and electrical works.	Item No. G.2.  <i>Supply/Installation of inverter ACU (2Hp) including rough-in and electrical works.</i>
<i>N.B. Please use the attached revised Specifications as attachment for TAB H of the eligibility and technical documents.</i>	

Please be guided accordingly.

  
**ASEC. JOSUE S. GAVERZA, JR.**  
 Chairperson, DWD Proper BAC

## *Section VI. Specifications*

ITEM	DESCRIPTION	STATE "Comply" or "Not Comply"
<b>A</b>	<b>SITE INSPECTION</b>	
1	The contractors/bidders shall conduct site survey/ocular inspection to assess and evaluate the site condition, works to be done as reference for bid estimate and execution.	
<b>B</b>	<b>DEMOLITION/REMOVAL/RELOCATION WORKS</b>	
1	Demolition/Removal of all existing low partition	
2	Demolition/Removal of wall.	
3	Demolition/Removal of doors.	
4	Demolished/Removal of worktop.	
5	Demolished/Removal of floor and wall tiles (C.R.).	
6	Demolished/Removal/Relocation of ACU.	
<b>C</b>	<b>PAINTING WORKS</b>	
1	Remove all loose, scaling, flaking and peeling off old paints.	
2	Surfaces should be clean and dry, free from dust, dirt and other foreign matter.	
3	Apply patching compound, boral or putty and sanding to eliminate un-even surfaces.	
4	Apply anti-rust solution for steel surface preparation.	
5	Apply three (3) coats of paints including priming to ensure good quality finish.	
6	Use Quick Dry Enamel (QDE) for wooden surfaces and semi-gloss latex for concrete including fibercement board and/or hardiflex.	
7	Use odorless paint and color shall be submitted for approval prior to application (mock-up shall be done if necessary).	
8	Re-varnishing of existing cabinets, cornices, baseboard and others.	
<b>D</b>	<b>TILES WORKS</b>	
1	Repair/Replacement of damaged floor tiles. Use the same size, color and design.	
2	Supply/Installation of 600mm x 600mm semi-granite floor tiles and 300mm x 600mm semi-granite wall tiles at CRs. Color and design for approval by the implementing office.	
3	Before the installation of floor tiles, the contractor shall conduct a water test in all concrete slab surfaces to check if the areas are ready and secured for possible water leak. And if were found, the contractor are mandated to act for a mitigating measure by applying water proofing or other procedure before the tiles was laid. This is to protect/avoid ceiling/electrical damages in the year comes.	
<b>E</b>	<b>DOOR &amp; HARDWARES</b>	
1	Supply/installation of 0.90m x 2.10m solid panel double door with door jamb, heavy duty door hinges/closer, 2 pieces of door knob or approved as equivalent.	
2	Supply/installation of 0.80m x 2.10m flush door with door jamb, heavy duty door closer, door hinges and door knob or approved as equivalent.	
3	Supply/Installation of sliding door with mechanism, running rail and other consumables to complete the installation.	
4	Submittals: Submit Manufacturer's product data and instructions for hardware and other pre-manufactured finishes and accessories	
5	Shop Drawings:	
	Mortise-type door lock with dead bolt	
	Door Closer – with hold-open feature, heavy duty up to 80kg	

	Hinges – 4" x 4" x 3.0mm thick, ball bearing type, stainless steel, satin finish.	
	Lever-Type Door Lock – stainless steel, satin finish, heavy duty	
	Dead Bolt – Heavy duty, satin finish	
	Barrel Bolt - Heavy duty, satin finish	
6	All hardwares shall be of the same Brand Manufactures.	
<b>F</b>	<b>CARPENTRY WORKS</b>	
1	For dry wall (double wall partition and low partition) use ¼ fiber-cement board. Use 2"x3"x10'x1.0mm metal tracks and studs at 0.60m x 0.60m spacing on center.	
2	For cabinets/drawer use ¾ HDF melamine board, concealed hinges, stainless steel handle, lock, catch and other consumables to complete the installation. Cut edges shall be finished with pvc edging using contact cement.	
3	For table and worktop use ¾ HDF melamine board. Use 12" steel bracket as support. Color and design texture as per approved by the implementing office.	
4	Supply/Installation of secret door use ¼ plywood, good lumber, decorative molding, hinges, door closer and other consumables to complete the installation.	
<b>G</b>	<b>ELECTRICAL WORKS</b>	
1	Supply/Installation of convenience outlet for all working rooms/stations.	
2	Supply/Installation of inverter ACU including rough-in and electrical works.	
3	Supply/Installation of wall type exhaust fan including rough-in and electrical works.	
4	Supply/Installation of LED fluorescent tube 18w (single end connection) with switch and plate.	
5	Use THHN wire, 3.5mm <sup>2</sup> #12 AWG (std)	
6	All fixtures 220V.	
<b>H</b>	<b>PLUMBING/SANITARY WORKS</b>	
1	All plumbing works shall be done in accordance with the provision of National Plumbing Code.	
2	Provide 50mm p-trap for every 100mm x 100mm floor drain.	
3	Horizontal piping shall be run in straight line and have a minimum slope as follows:65mm diameter pipe and smaller than 0.0063 fall per foot except where the condition do not permit fall of 0.0032 per foot, a lesser slope will be permitted. Provide a velocity of 0.60 per second with drain.	
4	All joint connection shall use quality adhesive and sealant to avoid leakage. Good workmanship is expected during the installation.	
<b>I</b>	<b>SUPPLY / INSTALLATION OF TELEPHONE AND INTERNET CONNECTION</b>	
1	Supply/Installation of internet connection for all working room and/or working stations.	
2	Provision of telephone outlet (2 sets each for Chief of Office and working area)	
3	Hide unsightly cords/cables/wires	
<b>J</b>	<b>SUPPLY/INSTALLATION OF ALUMINUM WINDOW (ANALOK) WITH ¼" THICK GLASS</b>	
1	Aluminum window (analok) with ¼" thick clear glass (90cmx90cm).	
<b>K</b>	<b>SUPPLY/INSTALLATION OF ACCORDION WALL</b>	
1	Supply/Installation of pvc accordion wall	
<b>L</b>	<b>SUPPLY/INSTALLATION OF WALL MOUNTED 6mm TEMPERED GLASS WRITING BOARD</b>	
1	Supply/Installation of wall mounted 6mm tempered glass writing board (H1.20mxL1.60m)	
2	Magnetic tempered glass writing board – without holes.	
3	Without pre-drilled holes, c/w stainless steel mounting brackets	
4	White backing	
5	Polished edges and radius rounded corners	
6	Glass thickness: 6mm	

7	Magnetic (able to hold strong magnet)	
8	Standard c/w 30cm length glass pen-tray and 2 nos. of strong magnet button.	
<b>M</b>	<b>SUPPLY AND DELIVERY OF TABLE AND CHAIR</b>	
1	Executive Table (L160 x W60 x H75cm) from melamine panel/board (HDF) with top drawer and 2 sides 3 drawer cabinets. Color and design texture as per approved by the implementing office.	
2	Eight (8) seater dining table with chair.	
<b>N</b>	<b>CLEARING AND DISPOSAL</b>	
1	Before and after working hour, contractors shall always conduct and maintain cleanliness on working areas for safety and efficient movement of workers or any person who were using the place.	
2	After completion of works, all refuse and garbage shall be clear, transport and dump to the contractor dumping site or otherwise area allocated by the implementing office, at contractor's expense.	
<b>O</b>	<b>OTHERS</b>	
1	All purchase but not limited materials to be installed shall have an approved sample/brochure before the final installation as follows: water closet, lavatory, tiles, chairs, roll-up blinds, doors and others.	
2	Implementing office/representative together with the contractor will conduct preliminary inspection and punch listing after declaring completed, before the final acceptance.	

Note:

Bidder shall affirm with this form/section complying with all the specifications, and which shall be submitted/placed/enclosed under Technical Documents Envelop.

Name: \_\_\_\_\_

In the capacity of: \_\_\_\_\_

Signed: \_\_\_\_\_

Duly authorized to sign the Bid for and on behalf of: \_\_\_\_\_

Date: \_\_\_\_\_